



# OFFICE OF THE PRINCIPAL DARRANG COLLEGE, Tezpur-784001

## NOTICE INVITING QUOTATION

Ref No: -Q/2023-24/DC/OCT/05

Date: -12.10.2023


Sealed quotation are invited by the undersigned affixing court fee Rs. 8.25 from the reputed firms for the following works of Darrang College, Tezpur, within 10 days from the issue of this notice. The rate must be quoted including the applicable GST and the quotations must reach the office of the undersigned on or before 22.10.23. The quotations will be opened at Principals Meeting Room on 23.10.23.

### Categories of work: -

1. P&F of Furniture, renovation, redesigning of the new Principal Office, visitor room and toilet etc. including dismantling, electrical, furnishing flooring etc. on turnkey basis. (Details of BOQ is attached)
2. P&F of acoustic wall paneling, floor gradient, carpeting, stage crafting, seating etc. in the new Seminar Hall in the campus on turnkey basis. (Details of BOQ is attached)

Copy to: -

1. Notice board for display.
2. Guard file.

  
(Dr. Palash Moni Saikia)  
Principal,  
Darrang College, Tezpur  
Principal  
Darrang College  
Tezpur, Assam

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

### PRINCIPAL CABIN

Sr. No.	DESCRIPTION OF WORK	Qty	UNIT	Rate	Amount
<b>1</b>	<b>DISMANTLING JOB</b>				
	Breaking the existing brick / concrete/ siporex wall, counter, flooring, removing the doors with door frames, windows, grills, Aluminium partition etc. and taking away the useful materials such as doors etc. without damage and disturbing the structure. Setting right the surfaces by plastering, punning etc. all complete including carting away the debris to a place approved by Municipal Corporation / Local Authorities a) Flooring, floor b) Aluminum/wooden partition, door c) Brick wall d) Old Electrical wiring and switch board.	L.S	1		
<b>2</b>	<b>VITRIFIED TILE FLOORING</b>				
	Providing and fixing first quality vitrified tiles homogenous body on floor of approved make, of H.R. Johnson. Marbitto or kajaria of approved colour Marbitto or kajaria of approved colour design and shade and of size 605 to 605 mm x 605 to 605 mm having modulus of rupture greater than 500 kg / cm <sup>2</sup> and modulus of hardness 8.0 with variation in size less than 0.05% in approved colour, design and size in cement mortar bedding avg. 40 mm thk. in C:M 1:4 with neat white cement slurry fixed in correct line, level in approved design and pattern.	sqm	29		
<b>3</b>	<b>PANELLING LAMINATE:</b>				
	Providing and fixing Assam or Malaysian Sal / Hard wood or equivalent quality wooden members of size 50 mm x 25 mm (to level the surface). The spacing of wooden members shall be 600 c/c both ways with necessary anti termite treatment. Providing and fixing 6 mm thick Commercial plywood MR grade as per BIS 303 (silver MR Grade) to the frame work. Providing and fixing 1.00 mm thick laminate of approved make, design colour and pattern with the help of suitable adhesive of approved make all complete.	sqm	60		
<b>4</b>	<b>FALSE CEILING :</b>				
	Providing and fixing in position suspended false ceiling consisting of the following G.I. sections manufactured by M/s. Saint Gobin Vertical suspenders of angle section, peripheral channels, primary and secondary frame work at centre to centre distance of 600 mm maximum of 'C' channels, the suspenders to be fixed with the ceiling with the help of angle cleats and expansion bolts. The peripheral channels to be screwed to the wall with the help of metal screws, the junction of peripheral channels and primary / secondary channels to be screwed with suitable metal screws. The junctions of primary and secondary channels to have G.I. clips. Providing and fixing 12 mm thick double skin gypsum board manufactured by M/s. India Gypsum Ltd with the help of suitable screws in line and level.	sqm	15		
<b>5</b>	<b>MINERAL FIBRE BOARD FALSE CEILING :</b>				

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

	Supplying, fitting and fixing mineral fibre acoustic suspended ceiling system fine fissured Dune edge tiles with Armstrong XL 24mm exposed grid. The tiles should have humidity resistance of 99%, NRC 0.55, light refraction 85% thermal conductivity 0.052-0.057 w/mk, in module size 600mm x 600mm x 13mm. The grid should have standard T section having rotary stitching on all T section and appropriate load capacity and proper Galvanising complete as directed and specified.	sqm	17		
<b>6</b>	<b>TOUGHENED GLASS (12 MM THICK) PARTITION</b>				
	Providing & Fixing fully Glazed frame less partition in between visitor room & Principal cabin with made of 12 mm thick toughened glass with frosted film.	sqm	6		
<b>7</b>	<b>TOUGHENED GLASS (12 MM THICK) DOOR</b>				
	Providing & Fixing fully Glazed frame less door made out of 12 mm thick toughened glass and the door to be fixed with a ozone floors springs with stainless steel finish patch fittings on top, bottom and lock of ozone make. The door also have a lock on bottoms and 450 mm to 600 mm length stainless steel brush finish handles of 25 mm dia complete jobs	sqm	2		
<b>8</b>	<b>PARTLY GLAZED DOOR</b>				
	Providing & Fixing flush door of thickness 30 mm to 36 mm raw size of approved make together with existing fram. The shutter may be finished with 1mm thick laminate in approved make, shade and design on both side. This item is included 6mm clear float glass and it should be fixed with suitable T.W. Beadings. The wooden surface to be finished with 3 coat of melamine polish of approved colour and shade. Providing and fixing teak wood beading to the edges, providing and fixing hardware fixtures and fittings in heavy duty SS such as lock of 6 lever locks with handles in S. S. finish of approved model of make of godrej/door set or equivalent tower bolt, hinges, handle, door stopper, incl. door closer of approved make etc. The item includes polishing the edges of the shutter.	sqm	4.5		
<b>9</b>	<b>PAINT &amp; PUTTY WORKS</b>	sqm	60		
	Applying Acrylic Emulsion with primer of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Client) : (Two coats)i) Standard Quality				
<b>10</b>	<b>ELECTRICAL WORKS</b>				
	Providing & Fixing Compact Fluorescent Lamp 6" dia round Ceiling Lights including lamps, fittings & all conduiting/F.R cabling&wiring/Modular switch & connections required to complete the job. ( Light-Crompton/Havells/Phillips/Wipro) (switch-Crabtree/Anchor/GM) (Wire- Havells,Finolex,Glowstar,Polycab,RR cable)	sqm	29		
<b>a)</b>	Providing and fixing of 36W 2'X2' LED square light fittings	nos	6		
<b>b)</b>	LED 12 watt LED round light.	nos	20		
<b>11</b>	<b>FURNITURE</b>				
<b>a)</b>	Principal table (Size-1800X900x750mm)	nos	1		
<b>b)</b>	Side Unit (Size-1200X400x750mm)	nos	1		
<b>c)</b>	Book rack (Size-2100X450x2400mm)	nos	1		
<b>d)</b>	Back unit (Size-1800X400x2100mm)	nos	1		
<b>e)</b>	Principal Chair	nos	1		
<b>f)</b>	Visitor Chair	nos	3		

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

g)	3 seater Sofa	nos	2		
h)	Center table(Size-900x450x450)	nos	2		
1	<b>Quantity mentioned are on approximate basis, actual work done measurement will be considered.</b>				
2	<b>Appropriate GST to be charged and shown separately.</b>				
3	<b>List of materials to be used should get approval from the authority before use.</b>				
4	<b>Layout plan, scheme and design of the overall work to be presented to the authority and get approval.</b>				
5	<b>Due to the priority of completeion, earliest delivery will be preferred.</b>				

### PRINCIPAL VISITOR ROOM

Sr. No.	DESCRIPTION OF WORK	Qty	UNIT	Rate	Amount
	<b>DISMANTLING JOB</b>				
	Breaking the existing brick / concrete/ siporex wall, counter, flooring, removing the doors with door frames, windows, grills, Aluminium partition etc. and taking away the useful materials such as doors etc. without damage and disturbing the structure. Setting right the surfaces by plastering, punning etc. all complete including carting away the debris to a place approved by Municipal Corporation / Local Authorities a) Flooring, floor Aluminum/wooden partition, door Brick wall Electrical wiring and switch board.	L.S	1		
	<b>VITRIFIED TILE FLOORING</b>				
	Providing and fixing first quality vitrified tiles homogenous body on floor of approved make, of H.R. Johnson. Marbita or kajaria of approved colour Marbita or kajaria of approved colour design and shade and of size 605 to 605 mm x 605 to 605 mm having modulus of rupture greater than 500 kg / cm <sup>2</sup> and modulus of hardness 8.0 with variation in size less than 0.05% in approved colour, design and size in cement mortar bedding avg. 40 mm thk. in C:M 1:4 with neat white cement slurry fixed in correct line, level in approved design and pattern.	sqm	19		
	<b>PANELLING LAMINATE:</b>				
	Providing and fixing Assam or Malaysian Sal / Hard wood or equivalent quality wooden members of size 50 mm x 25 mm (to level the surface). The spacing of wooden members shall be 600 c/c both ways with necessary anti termite treatment. Providing and fixing 6 mm thick Commercial plywood MR grade as per BIS 303 (silver MR Grade) to the frame work. Providing and fixing 1.00 mm thick laminate of approved make, design colour and pattern with the help of suitable adhesive of approved make all complete.	sqm	23		
	<b>FALSE CEILING :</b>				

**Office of the principal :: Darrang College :: Tezpur**

**BOQ OF PRINCIPAL OFFICE**

	<p>Providing and fixing in position suspended false ceiling consisting of the following G.I. sections manufactured by M/s. Saint Gobin Vertical suspenders of angle section, peripheral channels, primary and secondary frame work at centre to centre distance of 600 mm maximum of 'C' channels, the suspenders to be fixed with the ceiling with the help of angle cleats and expansion bolts. The peripheral channels to be screwed to the wall with the help of metal screws, the junction of peripheral channels and primary / secondary channels to be screwed with suitable metal screws. The junctions of primary and secondary channels to have G.I. clips. Providing and fixing 12 mm thick double skin gypsum board manufactured by M/s. India Gypsum Ltd with the help of suitable screws in line and level.</p>	sqm	13	
<b>MINERAL FIBRE BOARD FALSE CEILING :</b>				
	<p>Supplying, fitting and fixing mineral fibre acoustic suspended ceiling system fine fissured Dune edge tiles with Armstrong XL 24mm exposed grid. The tiles should have humidity resistance of 99%, NRC 0.55, light refraction 85% thermal conductivity 0.052-0.057 w/mk, in module size 600mm x 600mm x 13mm. The grid should have standard T section having rotary stitching on all T section and appropriate load capacity and proper Galvanising complete as directed and specified.</p>	sqm	8.6	
<b>PARTLY GLAZED DOOR</b>				
	<p>Providing &amp; Fixing flush door of thickness 30 mm to 36 mm raw size of approved make together with existing fram. The shutter may be finished with 1mm thick laminate in approved make, shade and design on both side. This item is included 6mm clear float glass and it should be fixed with suitable T.W. Beadings. The wooden surface to be finished with 3 coat of melamine polish of approved colour and shade. Providing and fixing teak wood beading to the edges, providing and fixing hardware fixtures and fittings in heavy duty SS such as lock of 6 lever locks with handles in S. S. finish of approved model of make of godrej/door set or equivalent tower bolt, hinges, handle, door stopper, incl. door closer of approved make etc. The item includes polishing the edges of the shutter.</p>	sqm	4.5	
<b>PAINT &amp; PUTTY WORKS</b>		sqm	40	
	<p>Applying Acrylic Emulsion with primer of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Client) : (Two coats)i) Standard Quality</p>			
<b>ELECTRICAL WORKS</b>				
	<p>Providing &amp; Fixing Compact Fluorescent Lamp 6" dia round Ceiling Lights including lamps, fittings &amp; all conduiting/F.R cabling&amp;wiring/Modular switch &amp; connections required to complete the job. ( Light-Crompton/Havells/Phillips/Wipro) (switch-Crabtree/Anchor/GM) (Wire- Havells,Finolex,Glowstar,Polycab,RR cable)</p>	sqm	19	
	<p>Providing and fixing of 36W 2'X2' LED square light fittings</p>	nos	5	
<b>b)</b>	<p>LED 12 watt LED round light.</p>	nos	10	
<b>FURNITURE</b>				

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

Principal PA table (Size-1200X600)	nos	1		
Side Unit (Size-900X400)	nos	1		
PA Chair	nos	1		
3 seater Sofa	nos	2		
Center table(Size-900x450x450)	nos	2		

### PRINCIPAL ROOM PANTRY & PASSAGE

Sr. No.	DESCRIPTION OF WORK	UNIT	QNTY	Rate	Amount
	<b>DISMANTLING JOB</b>				
	Breaking the existing brick / concrete/ siporex wall, counter, flooring, removing the doors with door frames, windows, grills, Aluminium partition etc. and taking away the useful materials such as doors etc. without damage and disturbing the structure. Setting right the surfaces by plastering, punning etc. all complete including carting away the debris to a place approved by Municipal Corporation / Local Authorities a) Flooring, floor b) Aluminum/wooden partition, door c) Brick wall d)Old Electrical wireing and switch board.	L.S	1		
	<b>INTERNAL PLASTER WITH DAMP PROOFING COMPOUND :</b>				
	Removing of existing wall plaster and providing and applying damp proof plaster 15mm to 18 mm thick, 1:4 mixed with liquid integral damp proofing compound Sika make or equivalent approved by the Consultan Engineer-in-charge.	sqm	10		
	<b>PANTRY COUNTER</b>				
	Providing and fixing pantry counter desired quality granite of 16 to 18mm thk of approved shade and colour for the , the marble to be fixed with cement mortar 1 : 4 and with required cement with one S/S sink.	nos	1.5		
	<b>VITRIFIED TILE FLOORING</b>				
	Providing and fixing first quality vitrified tiles homogenous body on floor of approved make, of H.R. Johnson, Marbito or kajaria of approved colour Marbito or kajaria of approved colour design and shade and of size 605 to 605 mm x 605 to 605 mm having modulus of rupture greater than 500 kg / cm <sup>2</sup> and modulus of hardness 8.0 with variation in size less than 0.05% in approved colour, design and size in cement mortar bedding avg. 40 mm thk. in C:M 1:4 with neat white cement slurry fixed in correct line, level in approved design and pattern.	sqm	19		
	<b>WALL TILES</b>				

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

Removing if any type of wall dado tiles carefully without damaging the structure and leveling the wall with applying cement plaster of 1 : 4 and Providing and fixing 1st quality ceramic tiles for wall dado of approved manufacturer such as NITCO/ Johnson ceramic of approved colour, design and size with neat cement slurry fixed in correct line, level and in plumb. The maximum variation from the stated size other than thickness shall be 1 mm, including pointing the joints with matching colour Roffe tile compound, cleaning the surface, curing, acid cleaning the tile work, etc., all complete, all as per directions of the Engineer-in-Charge. a) Tiles of size-300 x 450 mm	sqm	3		
<b>FALSE CEILING :</b>				
Providing and fixing in position suspended false ceiling consisting of the following G.I. sections manufactured by M/s. Saint Gobin Vertical suspenders of angle section, peripheral channels, primary and secondary frame work at centre to centre distance of 600 mm maximum of 'C' channels, the suspenders to be fixed with the ceiling with the help of angle cleats and expansion bolts. The peripheral channels to be screwed to the wall with the help of metal screws, the junction of peripheral channels and primary / secondary channels to be screwed with suitable metal screws. The junctions of primary and secondary channels to have G.I. clips. Providing and fixing 12 mm thick double skin gypsum board manufactured by M/s. India Gypsum Ltd with the help of suitable screws in line and level.	sqm	21		
<b>PARTLY GLAZED DOOR</b>				
Providing & Fixing flush door of thickness 30 mm to 36 mm raw size of approved make together with existing fram. The shutter may be finished with 1mm thick laminate in approved make, shade and design on both side. This item is included 6mm clear float glass and it should be fixed with suitable T.W. Beadings. The wooden surface to be finished with 3 coat of melamine polish of approved colour and shade .Providing and fixing teak wood beading to the edges, providing and fixing hardware fixtures and fittings in heavy duty SS such as lock of 6 lever locks with handles in S. S. finish of approved model of make of godrej/door set or equivalent tower bolt, hinges, handle, door stopper, incl. door closer of approved make etc. The item includes polishing the edges of the shutter.	sqm	2.8		
<b>PAINT &amp; PUTTY WORKS</b>				
Applying Acrylic Emulsion with primer of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Client) : (Two coats)i) Standard Quality	sqm	40		
<b>ELECTRICAL WORKS</b>				

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

Providing & Fixing Compact Fluorescent Lamp 6" dia round Ceiling Lights including lamps, fittings & all conduiting/F.R cabling&wiring/Modular switch & connections required to complete the job. ( Light-Crompton/Havells/Phillips/Wipro) (switch-Crabtree/Anchor/GM) (Wire- Havells,Finolex,Glowstar,Polycab,RR cable)	sqm	21		
Providing ,Fitting & Fixing 300 mm dia Exhaust Fan	nos	1		
12 watt 6" dia LED round Light	nos	10		
<b>FURNITURE</b>				
Pantry Stroage (size-L-1750xH-800XD-600)	nos	1		
Metal Stool	nos	2		

## PRINCIPAL ROOM TOILET

Sr. No.	DESCRIPTION OF WORK	UNIT	QNTY	Rate	Amount
1	<b>DISMANTLING JOB</b>				
	Breaking the existing brick / concrete/ siporex wall, counter, flooring, removing the doors with door frames, windows, grills, Aluminium partition etc. and taking away the useful materials such as doors etc. without damage and disturbing the structure. Setting right the surfaces by plastering, punning etc. all complete including carting away the debris to a place approved by Municipal Corporation / Local Authorities a) Flooring, floor Aluminum/wooden partition, door Brick wall Electrical wiring and switch board.	L.S	1		
2	<b>INTERNAL PLASTER WITH DAMP PROOFING COMPOUND :</b>				
	Removing of existing wall plaster and providing and applying damp proof plaster 15mm to 18 mm thick, 1:4 mixed with liquid integral damp proofing compound Sika make or equivalent approved by the Consultan Engineer-in-charge.	sqm	10		
3	<b>BESIN COUNTER</b>				
	Providing and fixing BESIN counter desired quality granite of 16 to 18mm thk of approved shade and colour for the , the marble to be fixed with cement mortar 1 : 4 and with required cement.	nos	2.4		
4	<b>VITRIFIED TILE FLOORING</b>				
	Providing and fixing first quality anty skied vitrified tiles homogenous body on floor of approved make, of H.R. Johnson. Marbito or kajaria of approved colour Marbito or kajaria of approved colour design and shade and of size 605 to 605 mm x 605 to 605 mm having modulus of rupture greater than 500 kg / cm2 and modulus of hardness 8.0 with variation in size less than 0.05% in approved colour, design and size in cement mortar bedding avg. 40 mm thk. in C:M 1:4 with neat white cement slurry fixed in correct line, level in approved design and pattern.	sqm	9		
5	<b>WALL TILES</b>				



**Office of the principal :: Darrang College :: Tezpur**

**BOQ OF PRINCIPAL OFFICE**

	Removing if any type of wall dado tiles carefully without damaging the structure and leveling the wall with applying cement plaster of 1 : 4 and Providing and fixing 1st quality ceramic tiles for wall dado of approved manufacturer such as NITCO/ Johnson ceramic of approved colour, design and size with neat cement slurry fixed in correct line, level and in plumb. The maximum variation from the stated size other than thickness shall be 1 mm, including pointing the joints with matching colour Roffe tile compound, cleaning the surface, curing, acid cleaning the tile work, etc., all complete, all as per directions of the Engineer-in-Charge. a) Tiles of size-300 x 450 mm	sqm	30		
<b>6</b>	<b>FALSE CEILING :</b>				
	Providing and fixing in position suspended false ceiling consisting of the following G.I. sections manufactured by M/s. Saint Gobin Vertical suspenders of angle section, peripheral channels, primary and secondary frame work at centre to centre distance of 600 mm maximum of 'C' channels, the suspenders to be fixed with the ceiling with the help of angle cleats and expansion bolts. The peripheral channels to be screwed to the wall with the help of metal screws, the junction of peripheral channels and primary / secondary channels to be screwed with suitable metal screws. The junctions of primary and secondary channels to have G.I. clips. Providing and fixing 12 mm thick double skin gypsum board manufactured by M/s. India Gypsum Ltd with the help of suitable screws in line and level.	sqm	10		
<b>7</b>	<b>PARTLY GLAZED DOOR</b>				
	Providing & Fixing flush door of thickness 30 mm to 36 mm raw size of approved make together with existing fram. The shutter may be finished with 1mm thick laminate in approved make, shade and design on both side. This item is included 6mm clear float glass and it should be fixed with suitable T.W. Beadings. The wooden surface to be finished with 3 coat of melamine polish of approved colour and shade .Providing and fixing teak wood beading to the edges, providing and fixing hardware fixtures and fittings in heavy duty SS such as lock of 6 lever locks with handles in S. S. finish of approved model of make of godrej/door set or equivalent tower bolt, hinges, handle, door stopper, incl. door closer of approved make etc. The item includes polishing the edges of the shutter.	sqm	1.6		
<b>8</b>	<b>PAINT &amp; PUTTY WORKS</b>	sqm	25		
	Applying Acrylic Emulsion with primer of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Client) : (Two coats)i) Standard Quality				
<b>9</b>	<b>ELECTRICAL WORKS</b>				

# Office of the principal :: Darrang College :: Tezpur

## BOQ OF PRINCIPAL OFFICE

	Providing & Fixing Compact Fluorescent Lamp 6" dia round Ceiling Lights including lamps, fittings & all conduiting/F.R cabling&wiring/Modular switch & connections required to complete the job. ( Light-Crompton/Havells/Phillips/Wipro) (switch-Crabtree/Anchor/GM) (Wire- Havells,Finolex,Glowstar,Polycab,RR cable)	sqm	9		
a)	Providing ,Fitting & Fixing 300 mm dia Exhaust Fan	nos	1		
b)	LED 12 watt LED round light.	nos	6		
<b>10</b>	<b>BATH FITTING CHANGE</b>				
a)	10 litre White 5 star Gyser(AO SMITH/VENUS/BAJAJ)	nos	1		
b)		nos			
c)	Water Closet(HINDWARE/PARYWARE)	nos	1		
d)	Wash Besin(HINDWARE/PARYWARE WITH PEDESTAL)	nos	1		
e)	2 in 1 BIB COCK(HINDWARE/JAGUAR/ESSCO)	nos	1		
f)	Angular(HINDWARE/JAGUAR/ESSCO)	nos	6		
g)	Health Fauset(HINDWARE/JAGUAR)	nos	1		
h)	Besin Mixer (HINDWARE/JAGUAR/ESSCO)	nos	1		
i)	BottleTrap(HINDWARE/ESSCO)	nos	1		
j)	Towel Rack(Planet Platiniums/S/S)	nos	1		
		nos			
k)	Soap Dish (Planet Platiniums/S/S)	nos	2		
l)	Tissu Paper holder(Planet Platiniums/S/S)	nos	1		
m)	Besin and W.C Connector pipe	nos	6		
n)	Mirror(Size-6'X3') with 12mm thick ply backside	nos	1		
o)	SUPPLY & FIXING PVC. UPVC & CPVC. PIPE WITH L-BOW,T, PASS OVER & BRICK WALL GROOVE CUTTING & FILLING INCLUDING LABOUR CHARGE.	LS	1		



Dr. Palash Moni Saikia  
Principal,  
Darrang College, Tezpur  
Principal  
Darrang College  
Tezpur, Assam

Office of the principal :: Darrang College :: Tezpur

BOQ OF SEMINAR HALL

Interior, Furnishing and Furniture work in the Seminar Hall of Darrang College, Tezpur


Sr.No.	DESCRIPTION OF WORK	Quantity	UNIT	Rate Rs.	Amount(Rs)
1	<b>Acoustic Treatment of Lower part of side walls,back wall,fascia of the main hall and stage portion.</b>	130	Sqm.		
	Providing,fitting, fixing of wall panel for acoustic treatment upto an average hight of 1.2 m from floor of the Middle level. Providing the wooden/Galvanized Iron frame made 50 mm x 50 mm sections both ways at 600 mm grid to be fixed on the wall (Masonry / Concrete) with the help of bobbins of variable depth at every joints of the wooden frame/GI of the main hall so as to give a smooth alignment of the wall. The lower part wooden/GI fram covered by 6 mm thick MR ply and finish will be 3mm thick venner.Venner finish by malamain polish				

<b>2</b>	<b>Acoustic Treatment of Upper part of side wall/Back wall of the main hall and stage portion.</b>	<b>235</b>	<b>Sqm.</b>		
	Providing, fitting, fixing of wall panel for acoustic treatment upto an average height of 1.0 m from top of the Middle level. The wooden frame made up of Hard wood /Galvanized Iron 50 mm x 50 mm sections both ways at 600 mm grid to be fixed on the wall (Masonry / Concrete) with the help of bobbins of variable depth at every joints of the wooden frame of the main hall so as to give a smooth alignment of the wall.				
	Thereafter providing 50 mm thick Glass wool slab having density 16 kg/cum tie up with the wooden /GI frame by galvanised wire mesh and galvanised wire to avoid sagging of glass wool On top glass wool providing 12.5 mm thick gypsum board panel ( conforming to IS: 2095-1982 ) of 15% perforation or necessary perforation / fully fissured with asthetic decoration fixed with dry wall screw of 25 mm long 300 mm centre to centre apart. Finally the face layers of the boards are to be joined so as to have a finished flushed look which includes filling and finishing with jointing compounds, jointing tape complete.				
<b>3</b>	<b>Carpet Flooring of main hall</b>	<b>280</b>	<b>Sqm.</b>		
	Providing and Fixing of Design looppile carpet with all wall side wooden beading on steps to prevent from folds etc.(size 500 mmX500 mm)				
<b>4</b>	<b>Wooden Flooring of Stage Area</b>	<b>55</b>	<b>Sqm.</b>		
	Providing and Fixing and Fitting of wooden flooring, medium commercial with HDF board of size 1212x195 of thickness 8.3mm. The fitting system will be glueless all complete with skirting etc.				

<b>5</b>	<b>Seating Arrangements of the stage portion.</b>	<b>6</b>	<b>Nos</b>		
	Providing and Placing of chairs with 5 legs, chromium base stand with double whelled castors,with gas lifting and push back locking system,seat and back with HD foam and pin hole rubber upholstered with artificial leatherlite.				
<b>6</b>	<b>Table Arrangements of the Stage Portion.</b>	<b>1</b>	<b>nos</b>		
	Providing, fitting and Fixing tables made of water proof Blockboard 3/4" thickness.The sides,top and partition to be 1.5" thick and back to be 3/4" thick.The top layer to be fixed with white cedar ply which is to be polished or lacquered all complete with moukding etc.All exposed area will be finish with 1 mm thick decorative laminate(L20'XW2'XH2'6")				
<b>7</b>	<b>Wooden Stage</b>	<b>40</b>	<b>Sqm.</b>		
	Providing, fitting and Fixing wooden stage with made of water proof solid plywood 3/4" thickness. The framing of the stage will be made of 25 mmX 25 mm holo MS tube center to center 300mmX300mm grid.				
	<b>Wooden Gradient Student Seating area</b>	<b>150</b>			
	Providing, fitting and Fixing wooden stage with made of water proof solid plywood 3/4" thickness. The framing of the stage will be made of 25 mmX 25 mm holo MS tube center to center 300mmX300mm grid.				
<b>8</b>	<b>Flush Doors</b>	<b>24</b>	<b>Sqm.</b>		
	Providing and fixing of wooden flash door of 35mm thickness all visiable area will be finish 4 thick veener with franch polished finish all complete with SAL wood frame and necessary fitting, locks etc.The frame will be of SAL wood.				
<b>9</b>	<b>Desklet Chair</b>				
	The Base frame will have to be fabricated with 25mm powder coated MS pipe. The base of the seat and back will be of PLP board with cushioned seat and cushioned back. The chair will have one no of 18mm thick PLP board open able top including PVC edging fitted with good quality hinged on RHS screwed to 25mm hollow steel pipe inserted in 20mm MS rod welded to frame	<b>225</b>	<b>nos</b>		
<b>10</b>	<b>Digital Podium + Large Display Screen + Audio System</b>	<b>1</b>	<b>L.S.</b>		
	P&F of Bets quality digital podium set complete with all along with display screes of 96inch and matching and required quality of audio system for the hall of brand like Globus or'equivalent.				

11	<b>Curtains for Doors</b>	6	Nos.		
	Providing curtains of heavy furnishing cloth with marking, matching with the interior decoration including fixing of same with necessary fixing arrangements.				
12	<b>Scaffolding</b>				
	Providing, fitting & fixing of MS round pipe /Bamboo scaffolding with suitable nut & bolt	350	Sqm.		
13	Applying Acrylic Emulsion with primer of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Client) : (Two coats)i Standard Quality	620	Sqm.		

- 1 Quantity mentioned are on approximate basis, actual work done measurement will be considered.
- 2 Appropriate GST to be charged and shown separately.
- 3 List of materials to be used should get approval from the authority before use.
- 4 Layout plan, scheme and design of the overall work to be presented to the authority and get approval.
- 5 Due to the priority of completeion, earliest delivery will be preferred.

  
 Dr. Palash Moni Saikia  
 Principal,  
 Darrang College, Tezpur  
 Principal  
 Darrang College  
 Tezpur, Assam